

Leonard Dudzinski RPS Program Executive RPS Status for VEXAG November 2012




MMRTG F1




National Aeronautics and Space Administration

MMRTG Forward

- F2 demonstrated good performance (in storage)
- F3 to be completed 2013
- DOE Teledyne Contract Ends June 2013
- Investigating sustainment path forward
- Potential integration of advanced thermocouples into MMRTG body
 - Potential improved system efficiency > 9%






Pu-238 Domestic Production Status

- NASA Authorization Act of 2010 authorized NASA to fund DOE efforts in Pu-238 Production under a reimbursable agreement.
- DOE has begun a multi-phase Plutonium-238 Supply Project consistent with the published Start-up Plan to achieve full-scale production late in the decade.
- Phase I efforts to be completed by December 2012.
 - Project planning, NEPA assessment, analysis of project alternatives, cost and schedule estimate
- Technology demonstration efforts will achieve by the end of 2013:
 - A qualified neptunium-237 target for irradiation in the High Flux Isotope Reactor (*target currently in reactor*)
 - A qualified process for post-irradiation target processing
 - A qualified Pu-238 product
 - A project plan for scale-up to full-scale production at 1.5-2.0 kg/year
- PPBE FY15 will take into account NASA fully funding Pu-238 production



Advanced Stirling Radioisotope Generator (ASRG)

- ASRG provides increased efficiency (4X current)
- Offered as GFE in Discovery 12
- Highly enabling for science missions
- Conducted Final Design Review in July 2012
- Engineering units in test
- Controller design modified to be more robust to radiation environment
- Qualification unit (QU) build in progress



ASRG Summary Specification

Parameter	ASRG
Power per Unit (BOM), (4° K, space vacuum)	128 We (1.5% reserve on 130We)
Power per Unit (BOM), (Mars avg. temp, CO ₂)	106.4 We (1.5% reserve on 108 We)
Voltage	22-34 VDC (Nominal Range)
Power Degradation Rate, [%/yr]	~ 0.8 (power decays roughly with fuel decay)
Mass per Unit, [kg]	35.6 (includes 11% reserve on 32 kg) (1), (Includes ASRG to S/C power cables)
Dimensions for Generator Housing/Controller [cm]	L: 78 cm, W: 37.4 cm, H: 38.6 cm (GHA), L: 26.5 cm, W: 22.2 cm, H: 13.5 cm (ACU)
Radiation Tolerance	126 krad (2)
Additional Shielding, [kg]	Mission Specific, required only for controller in a high-radiation environment (3)
Number of GPHS Modules per Unit	2
Thermal Power (BOM), [Wt]	488-512 (min/max fuel load) (fuel processed in 2012)
Mechanical Disturbance (axial)	~ 22 N peak-peak (EU measured), (35 spec)
Frequency (Hz)	102
Controller	Single-fault tolerant, with N+1 redundant controller cards and the capability for the engines to operate independently of one another in the event of single engine failure.
External Radiator Temperature (4)	~ 45° C (space Vacuum, no Sun)
Operating Environment	Vacuum and Atmosphere (CO ₂)
Lifetime Requirement, [years]	14 + 3 (storage)

(1) Mass does not include: optional spacecraft adapter ring for missions using launch vehicles (> ~ 0.1 g/Hz); adds 1.23 kg; ~ 1 kg of telemetry cables not included.

(2) Radiation Tolerance: from 50kRad space and 13 kRad GPHS source Requirement, with RDF 2 applied

(3) For ASRG additional shielding is required to protect the controller electronics. (As an example, controller shielding mass for a Europa type mission was previously estimated at ~ 11 kg (TBR)).

(4) Case temperature for other environmental sink temperatures will vary

GPHS – General Purpose Heat Source BOM – Beginning of Mission

ASC Technology Development to Flight Evolution

	A. Tech. Development			B. Flight Transition		ו	C. Flight	
	ASC-1	ASC-0	ASC-1HS	ASC-E	ASC-E2	ASC-E3	ASRG	
	titt							
Material	MarM-247		MarM-247		MarM-247	MarM-247	MarM-247	
Wateria		IN718		Nº 18				
Hermetic		X	Х		х	Х	×	
Progress	 Demo high efficiency and Low Mass High temp components and joints demo. (HH, and Disp.) 	 Develop Hermetic Processes Identify and resolve developmen tal issues Initiated QA/process documents Extended Operation, in a 	 Demo Hermetic Processes en High tento units Improve prossing (trazes, gas bearings, etc.) Exended Operation, in thermal-vac 	 ASFG Legration Interfaces Major Improvement in quality & docs. Improve processing (i.e. Closure weld, flow bench, etc.) Configuration control (ERB) 	 Develop and Implement Quality Project Plan Based on DOE Nuclear standard Enhance interfaces Refine high temp. processes & joints Enhance reliability and manufacturability Infrastructure Dedicated Facility Design Software Laser Welder Inspection (CMM) Epoxy Mixer 	 Manufacture refinement as needed Refinement to Include any new mission or generator derived requirements LM, DOE, NASA, and SP joint product team 	NASA complete: Suppower ASC technolog; development and hands on to DOE for Flight implementation	
GRC/SP Contract						DOE/LM/SP Contract		

Progressive Refinement Towards Flight Implementation

ASRG QU, Demonstration, and GSE





EDU 3 Controller (ACU)

QU Inboard / Outboard Housings, Finish Machined




Fit Up Model GHA



Electrical Ground Support Equipment in Production

ASRG Forward

- Flight Systems
 - Fueled Qual Unit
 - F1 and F2 Unfueled
 Units by NLT 10/2016
 - Ready for D-13
 - Ready for NF-4
 - Ready for Mars 2018
 - Other
- "M1" Project
 - Integrate with S/C bus
 - Independent V&V




M1 Project Goals

- To be a platform to independently verify system-tospacecraft interface requirements and to validate integrated system performance
- To be a pathfinder for future missions regarding the integration, operation and use of an ASRG
- To assess and characterize the ASRGs for mission use
- To develop documentation to enable easier integration of the ASRG into future missions and future AO proposal cycles.

The program intends for the M1 project to fill the knowledge gaps lost with the Discovery12 flight opportunity. The RPS Program requires the ability to thoroughly benchmark, checkout, and integrate the ASRG in the same capacity if a planetary mission was receiving, integrating and utilizing two ASRG on a spacecraft.

ASRG/M1 Project Interactions



Hardware

***NOTIONAL Activity sequencing and duration

M1 Products & Outcomes

- Mission inputs to extended testing of ASRG qualification unit at INL
- Mission inputs to bonded storage of 2 ASRG flight units at INL
- Electrically-heated ASRG units (received from ASRG Project)
- Spacecraft integration test campaign
- ASRG durability and reliability risk reduction test campaign
- Improved system documentation for next Announcement of Opportunity or other mission opportunity
- System Integration Laboratory with spacecraft testbed

Key Messages

- The ASRG development status did not effect the Discovery 12 selection
- The ASRG flight specification for F1 and F2 has been frozen since 2010, and will remain so
- The RPS Program will continue to act as a surrogate mission for ASRG development through the implementation of the "M1" project
- The ASRG development will be completed on an appropriate schedule, with two flight units ready for fueling by October 2016
- Planetary Science Division is considering mission options for ASRG F1 and F2
 - Discovery 13 as GFE
 - Mars 2018 or 2020

